



Public Works Department Project Start Notification

Public Works Compound Stormwater System Modification

Project Schedule

July 10 , 2023

Construction Start Date

December 2 , 2023

Construction Completion Date

Project Contact Information:

Contractor
West Wind Contracting

Andre Boucher Phone:
954-961-7200

City of Hallandale Beach

Brightny Dorelus
Project Manager

Public Works Dept.
Office: 954-457-4607
bdorelus@cohb.org

Follow Us



www.cohb.org/projects

[Report a Concern via our MyHB App](#)

Background

The City of Hallandale Beach will be reconfiguring the Public Works Compound to better utilize the existing space. The City desires to fill in the area located in the northwest corner of DPW that is currently occupied by a stormwater retention pond. This area would be used for the City's sanitation fleet vehicles.

Scope of Work

The project includes the reconfiguration of current retention pond to be filled in and used as parking for the City's sanitation fleet vehicles. New parking lot scope includes grading, drainage, water and sewer piping and connections, and lighting. Drainage scope includes inlets, manholes, French drains, underground storage system, and dry retention swale. New parking lot will have a truck wash station with new water connection and catch basin equipped with an oil/water separator to be connected to the existing sewer. Concrete curbs, asphalt paving, signing and marking, sod and other miscellaneous improvements.

Project Status Update

Administrative Notice to Proceed was issued on June 5th, 2023 for the review of shop drawings and procurement of materials and equipment required for the construction of the project. The construction phase of the project is scheduled to commence on July 10, 2023, and completed by December 02, 2023

Project Limits/Proposed Location

